Name	Approved	Date
PA Eddy	PAE	7-22-83
PE Bramson	PEB	7-22-83

Project Number _____

Internal Distribution

PE Bramson
PA Eddy
FILE
LB

July 21, 1983

Vernon Steinhauer
Underground Surveys Corp.
4973 E. Lansing
P.O. Box 12891
Fresno, CA 93727

Dear Mr. Steinhauer:

I talked to Ben Everson on July 14 about building an aluminum light head with a compass mounted on the back of the light holder. The support rods from the viewing port to the light holder will have to be flush with the camera housing in order to pass through NX casing, which is 3 inches I.D. This unit should be pressure tested to withstand 2,000 psi.

I will need to know how long it will take to build this unit and also an estimate of the cost.

Very truly yours,

Vern L. McGhan
Sr. Technical Specialist
Environmental Evaluations Section

VLM:gd